Articulating Solar Panel Energy System (ASPEN), Phase I



Completed Technology Project (2018 - 2019)


Project Introduction

In response to NASA's need for a compact, low-cost and autonomous deployable solar array system to support Martian surface exploration, Roccor proposes to enhance the Mars Compact Telescoping Surface Array (CTSA) baseline design by incorporating an Articulating Solar Panel Energy System (ASPEN). The Mars CTSA was established in 2017 as the culmination of an extensive trade performed at NASA's Langley Research Center with the goal to support human Mars exploration. The ASPEN system includes PV cells bonded to a thin membrane that is z-folded while stowed, and pulled out / tensioned when deployed. The ASPEN system replaces traditional membrane PV blankets with lightweight panels that can be articulated in unison much like "Venetian blinds". This presence of articulation and resulting gaps between substrates offer unique advantages for operation on the Martian surface: 1) reduced cell density leading to increased performance in cost, W/kg and kW/m³, 2) implementation of array porosity and articulation control to reduce interaction with Martian wind and mitigate dust collection, and 3) modular design that enables mass production and ease of replacement.

Anticipated Benefits

The ASPEN technology is directly related to the ongoing development effort at the NASA Langley Research Center on the Mars Compact Telescoping Surface Array (CTSA) in support of human exploration of Mars. This effort will offer potential enhancements that will improve the baseline mission architecture.

The ASPEN technology enables rapid solar array pointing offering protection to harsh environments such as weather, debris or undesired electromagnetic radiation / directed energy. As such, this work is applicable to solar arrays deployed in harsh environments by both commercial and government defense agencies.



Articulating Solar Panel Energy System (ASPEN), Phase I

Table of Contents

Project Introduction	1
Anticipated Benefits	1
Primary U.S. Work Locations	
and Key Partners	2
Project Transitions	2
Organizational Responsibility	2
Project Management	2
Images	3
Technology Maturity (TRL)	3
Technology Areas	3
Target Destination	3




Articulating Solar Panel Energy System (ASPEN), Phase I



Completed Technology Project (2018 - 2019)

Primary U.S. Work Locations and Key Partners



Organizations Performing Work	Role	Туре	Location
Roccor, LLC	Lead Organization	Industry	Longmont, Colorado
Langley Research Center(LaRC)	Supporting Organization	NASA Center	Hampton, Virginia

Primary U.S. Work Locations	
Colorado	Virginia

Project Transitions

Ju

July 2018: Project Start



February 2019: Closed out

Closeout Documentation:

• Final Summary Chart(https://techport.nasa.gov/file/140934)

Organizational Responsibility

Responsible Mission Directorate:

Space Technology Mission Directorate (STMD)

Lead Organization:

Roccor, LLC

Responsible Program:

Small Business Innovation Research/Small Business Tech Transfer

Project Management

Program Director:

Jason L Kessler

Program Manager:

Carlos Torrez

Principal Investigator:

Dana Turse

Co-Investigator:

Dana Turse




Small Business Innovation Research/Small Business Tech Transfer

Articulating Solar Panel Energy System (ASPEN), Phase I




Completed Technology Project (2018 - 2019)

Images




Briefing Chart Image Articulating Solar Panel Energy System (ASPEN), Phase I (https://techport.nasa.gov/imag e/128267)



Final Summary Chart Image Articulating Solar Panel Energy System (ASPEN), Phase I (https://techport.nasa.gov/imag e/128269)

Technology Maturity (TRL)



Technology Areas

Primary:

- TX12 Materials, Structures, Mechanical Systems, and Manufacturing
 - └ TX12.3 Mechanical Systems
 - □ TX12.3.1 Deployables, Docking, and Interfaces

Target Destination

Mars

